



**SANTA ROSA COUNTY
PUBLIC WORKS DEPARTMENT**

STEPHEN FURMAN
Director
stephenf@santarosa.fl.gov

6075 Old Bagdad Highway | Milton, Florida 32583

MEMORANDUM

TO: Tony Gomillion, County Administrator
FROM: Stephen Furman, Public Works Director *SF*
DATE: Oct. 28, 2016
SUBJECT: District 3 Road Resurfacing Recommendations

RECOMMENDATION

Discussion of approval of resurfacing the following roads in District 3 at an estimated cost of \$438,050.00:

Cheyenne Drive	\$27,650.00
Country Squire Drive	\$30,970.00
Bayberry Street	\$28,850.00
Beaudry Lane (from Country Squire Drive for 765')	\$8,130.00
Bullard Road (from Hwy 87 to 5797 Bullard Rd.)	\$87,540.00
Evergreen Drive	\$ 21,570.00
Greenwood Drive	\$23,360.00
Homer Holland Road	\$15,000.00
Jesse Whitfield Road	\$70,300.00
Kembro Lane	\$28,200.00
Meadowlark Lane (from Starlight Ln to Northrop Ln)	\$30,220.00
Nutmeg Avenue	\$19,730.00
Sequoia Drive	\$18,880.00
Travis Bynum Road (from Mt. Carmel Rd., south 2,540 feet)	\$27,650.00

Total Estimated Cost **\$438,050.00**

BACKGROUND

The District 3 roads being recommended for resurfacing score high on our Road Rating criteria and/or score close enough to adjacent roadways that warrant resurfacing to recommend them for resurfacing at the same time.

District Three Resurfacing Recommendations

Cheyenne Drive	\$27,604.10
2105' x 18'	
95 tons SAHM @ 45 lbs. per yd ²	
253 tons SP-9.5 @ 120 lbs. per yd ²	
36 tons SP-9.5 for driveways	
10 tons SP-9.5 for intersections	
 Country Squire Drive	 \$30,966.60
2560' x 18'	
384 tons SP-12.5 @ 150 lbs. per yd ²	
44 tons SP-12.5 for driveways	
10 tons SP-12.5 for intersections	
 Bayberry Street	 \$28,844.60
2100' x 20'	
94 tons SAHM @ 40 lbs. per yd ²	
292 tons SP-9.5 @ 125 lbs. per yd ²	
15 tons SP-9.5 for driveways	
10 tons SP-9.5 for intersections	
 Beardry Lane (from Country Squire Drive for 765')	 \$8,130.50
765' x 18'	
115 tons SP- 12.5 @ 150 lbs. per yd ²	
 Bullard Road (from Hwy 87 to 5797)	 \$87,535.60
6590' x 18'	
264 tons SAHM @ 40 lbs. per yd ²	
989 tons SP- 12.5 @ 150 lbs. per yd ²	
15 tons SP-12.5 for driveways	
 Evergreen Drive	 \$ 21,562.40
1120' x 22'	
55 tons SAHM @ 40 lbs. per yd ²	
206 tons SP-12.5 @ 150 lbs. per yd ²	
20 tons SP-12.5 for driveways	
7 tons leveling for cul-de-sac	
24 tons surface for cul-de-sac	

Greenwood Drive

\$23,352.60

1750' x 20'

78 tons SAHM @ 40 lbs. per yd²235 tons SP- 9.5 @ 120 lbs. per yd²

20 tons SP-9.5 for driveways

Homer Holland Road

\$14,989.90

1300' x 15'

44 tons SAHM @ 40 lbs. per yd²163 tons SP- 12.5 @ 150 lbs. per yd²

10 tons SP-12.5 for driveways

Jesse Whitfield Road

\$70,284.60

5585' x 17'

211 tons SAHM @ 40 lbs. per yd²792 tons SP-12.5 @ 150 lbs. per yd²

10 tons SP-12.5 for driveways

5 tons SP-12.5 for intersections

Kembro Lane

\$28,138.60

2280' x 20'

380 tons SP-12.5 @ 150 lbs. per yd²

8 tons SP-12.5 for driveways

10 tons SP-12.5 for intersections

Meadowlark Lane (from Starlight Ln to Northrop Ln)

\$30,215.00

2180' x 21'

102 tons SAHM @ 40 lbs. per yd²305 tons SP- 9.5 @ 120 lbs. per yd²

24 tons SP-9.5 for driveways

Nutmeg Avenue

\$19,724.40

750' x 22'

138 tons SP-12.5 @ 150 lbs. per yd²

24 tons SP-12.5 for driveways

117 tons surface for cul-de-sac

Sequoia Drive

\$18,876.90

765' x 22'

140 tons SP-12.5 @ 150 lbs. per yd²

10 tons SP-12.5 for driveways

117 tons surface for cul-de-sac

Travis Bynum Road (from Mt. Carmel Rd. South 2,540 feet)

\$27,643.71

2540' x 18'

381 tons SP-12.5 @ 150 lbs. per yd²

10 tons SP-9.5 for driveways

Total Estimated Cost

\$437,869.51